

Table 3.4.1-2—Load Factors for Permanent Loads, γ_p

Type of Load, Foundation Type	Load Factor	
	Maximum	Minimum
<i>DC</i> : Component and Attachments	1.25	0.90
<i>DC</i> : Strength IV only	1.50	0.90
<i>DW</i> : Wearing Surfaces and Utilities	1.50	0.65
<i>EH</i> : Horizontal Earth Pressure		
• Active	1.50	0.90
• At-Rest	1.35	0.90
• Apparent earth pressure (<i>AEP</i>) for anchored walls	1.35	N/A
<i>EL</i> : Locked-in Construction Stresses	1.00	1.00
<i>EV</i> : Vertical Earth Pressure		
• Overall and Compound Stability	1.00	N/A
• Retaining Walls and Abutments	1.35	1.00
• MSE wall internal stability soil reinforcement loads		
○ Stiffness Method		
▪ Reinforcement and connection rupture	1.35	N/A
▪ Soil failure – geosynthetics (Service I)	1.20	N/A
○ Coherent Gravity Method	1.35	N/A
• Rigid Buried Structure	1.30	0.90
• Rigid Frames	1.35	0.90
• Flexible Buried Structures		
○ Metal Box Culverts, Structural Plate Culverts with Deep Corrugations, and Fiberglass Culverts	1.50	0.90
○ Thermoplastic Culverts	1.30	0.90
○ All others	1.95	0.90
• Internal and Compound Stability for Soil Failure in Soil Nail Walls	1.00	N/A
<i>ES</i> : Earth Surcharge	1.50	0.75

Table 3.4.1-3—Load Factors for PS, CR and SH, γ_p

Bridge Component	<i>PS</i>	<i>CR, SH</i>
Superstructures—Segmental	1.0	See γ_p for <i>DC</i> , Table 3.4.1-2
Concrete Substructures supporting Segmental Superstructures	1.0	See γ_p for <i>DC</i> , Table 3.4.1-2
Concrete Substructures supporting Segmental Superstructures when physical testing is performed to establish material properties and upper bound values are used in the analysis	1.0	1.0
Concrete Superstructures—nonsegmental	1.0	1.0
Concrete Substructures supporting non-segmental Superstructures	1.0	1.0
Steel Substructures	1.0	1.0

Table 3.4.1-4—Load Factors for Live Load for Service III Load Combination, γ_{LL}

Component	γ_{LL}
Prestressed concrete components designed using the refined estimates of time-dependent losses as specified in Article 5.9.3.4 in conjunction with taking advantage of the elastic gain	1.0
All other prestressed concrete components	0.8