

48. Walls adjacent to ponds are considered full height walls so long as the leveling pad is placed a minimum of 2 feet below the top of the adjacent maintenance berms.
49. Walls adjacent to the Right of Way shall consider the existing groundline outside of the Right of Way at natural grade. Internal and global stability of the walls shall be established based on existing conditions (i.e. existing terrain, existing ponds, etc.) outside of the Right of Way.
50. Wall Heights are limited to a maximum height as shown in SDG. Alternate wall types shall have an aesthetic finish consistent with the Project Aesthetic Requirements for MSE walls.
51. Tiered or terraced walls shall not be permitted for permanent walls. Refer to Figure 11.10.5.6-1 of the AASHTO LRFD Bridge Design Specifications (9th Edition) for an example of a tiered or terraced wall.
52. Limerock backfill in MSE walls is prohibited.

Miscellaneous Structures

53. The maximum truss height for overhead sign structures (Index No. 700-040, Index No. 700-041, or custom design) shall be 8'-0". In the event it is determined that the 8'-0" height limit cannot be met due to project design criteria, accommodations shall be provided to allow for climbing inspectors to reach the truss top chord member during future inspections.
54. Bridge traffic railing mounted supports for overhead sign structures shall not be permitted except at median traffic railings as shown in Index 521 001. At outside bridge traffic railings, overhead sign structure supports shall be mounted on pedestals behind the bridge traffic railings.
55. Traffic railing mounted supports for overhead sign structures on retaining walls shall not be permitted. Retaining wall mounted overhead sign structure supports shall be mounted on pedestals behind the traffic railings.

Structures Manual (SM) Modification for Non-Conventional Projects

The following sections of SM are to be modified as stated:

56. SDG 1.1.3.B.1 No bridges over navigable waterways.
57. SDG 1.3.1.A See RFQ for environmental classifications.
58. SDG 1.3.3.A Samples not required.
59. SDG 1.4.5 See RFQ for Class 5 Coating requirements.
60. SDG 1.5.A See Attachments of RFQ.
61. SDG 1.5.D No asbestos abatement plans are required.
62. SDG 2.1.2.A Paragraph SDG 2.1.2.A shall apply.
63. SDG 2.6.2 See RFQ for new pier requirements.
64. SDG 2.6.3 See RFQ for existing pier requirements.
65. SDG 2.6.3.A See RFQ for existing pier requirements.
66. SDG 2.10.B See RFQ for Operational Importance Factor.
67. SDG Table 3.5.1-1 Minimum concrete pile size is 18 inches.